Roofing Materials Required										Roof Area (Sq. ft) [5]	
	Asphalt Shingles (bndls) [1]			Cedar Shingles (bndls) [2]			Cedar Caps [3] (Incl. In cedar shingles total) [4]				
	Overhang Option		w/ Dormer	Overhang Option		w/ Dormer	Overhang Option		w/ Dormer	Overhang Option	
Unit size	*Std.*	*Extra +6"*		*Std.*	*Extra +6"*		*Std.*	*Extra +6"*		*Std.*	*Extra +6"*
8 ft	5	6	+2	7	8	+2	70	80	+12	83	103
9 ft	6	7	+2	9	10	+2	80	85	+13	103	124
10 ft	7	8	+2	10	10	+3	85	90	+14	124	148
11 ft	8	9	+3	11	11	+3	90	100	+15	148	174
12 ft	9	10	+3	12	12	+3	100	110	+16	174	202
14 ft	11	12	+4	14	15	+4	110	120	+17	231	263
16 ft	13	14	+4	16	18	+4	120	130	+17	n/a	333
18 ft	14	15	+5	18	22	+5	130	145	+18	n/a	411
20 ft	15	16	+5	20	27	+5	140	155	+18	n/a	498

Assumptions / Notes	
[1] Coverage per Asphalt Shingles (sq.ft.)	25
[2] Coverage per Cedar Shingles (sq.ft.)	20.375
[3] Cedar Caps per Bundle (ea.)	70
[4] The cedar caps shown are for your reference only; the cedar shingles list **does** include the caps in its total required bundles list. Also if you purchase your cedar shingles from us, we'll pre-cut the caps for you.	
[5] Roof Sq.ft. Estimated	